

RCU55

REMOTE CONTROLLED TRACKED CARRIERS

Compact Remote Controlled Carrier for Forestry, Agricultural and Municipal Applications.



FEATURES

STANDARD EQUIPMENT ON NZ MODELS

56 hp Rehlko (Kohler) turbocharged engine

Remote control unit with ergonomic joysticks and 4.3" display

Dual hydrostatic transmission

Hydraulic variable track system with automatic tensioning

High-profile heavy-duty rubber tracks

Auxiliary hydraulic circuits for multiple attachments

LED working lights

Heavy-duty steel undercarriage with independent frames

OPTIONS

High-profile steel tracks

Forestry protection kit (heavy-duty guarding)

Stage V/Tier 4F engine configurations



	HP Min	HP Max	Flow rate (L/min)	Pressure (bar)	Working width	Total width	Weight (kg)	No. of teeth
RCU55 (STAGE V/TIER 4F)	56	56	75	290	1240 - 1496	1532 - 1724	410 - 580	24

Data refers to machine without options

STANDARD MULCHER PACKAGE INCLUDES

Active VMA Remote Control Unit & Receiver Kit

Hydraulic Auxiliary Quick-Coupler Connections

Delivery, Driver Training, and Commissioning

ATTACHMENTS

ACTIVEVMA.CO.NZ

3-7 McCloskey Road, Rotorua 3015, New Zealand

07 345 5609 admin@activevma.co.nz

